minilec®

# INSTALLATION INSTRUCTION **CURRENT MONITORING RELAY**





OCS D1 offers protections against -Over current.

S2 CMR5 offers protections against -Under current. \* Over current.

These relay's are an auxiliary relay and it should be used along with the starter / contactor ckt. only The effective working of the unit will depend on efficient working of the starter. Before installing unit check whether the starter / ckt. is operating perfectly by starting with the "ON" push button and switching off by "OFF" push button. If the operation of START and STOP are imperfect the ckt. needs to be checked. Do not install your unit with faulty ckt.

#### CAUTION

- 1. Ensure that unit's are -\* Not installed near any heat sources like Burner, Sunlight, Electric arc etc.
- \* Not subjected to abnormal vibrations.
- \* Installed as near to starter as possible.
- \* Not subjected to Direct heat, Sunlight, Rain, Stormy wind and Dust.

2. Working of the product is affected by Supply or UPS Supply. Care should be taken to ensure that net resultant unbalance Supply is not beyond the unbalance trip limits of unit.

3. Program the S2 CMR5 only to suit your application. for programming S2 CMR5 only

4. If the product is not installed as per guideline given by Minilec. Company will not be responsible for any wrong connection, damage, Injury, accident, Etc.

#### ELECTRICAL CONNECTION

For installation of the unit in

# the power and control wiring.

PROGRAMMING / SETTING With the help of push button provided on front,

you can Program the relay for suitable operation.

#### MOUNTING -

All models are suitable for DIN RAIL mounting.

TE	CHNICAL SPECIFI	CATIONS OF OCS D1	MOUNTING DIMENSION	IS OCS D1	
	Auxilliam Sumply	110/220/230/240/380/415 VAC, + 20%	100 - 120, 220 - 240, 415 VAC± 20%		
1	Auximary Supply :	12/24 VDC. + 10%	24VDC ± 20%		
2	Rated Current Input :	(Selection via. Terminals) Terminal 1 & 2:Current Input 5 A/ (500 mA) Terminal 1 & 3:Current Input 1A/ (250 mA)	5Amp/ 1Amp (selection on terminal) Terminal 1 & 2 current input 5A (# 0.5A) Terminal 1 & 3 current input 1A (# 0.25A) (# - 0.5/0.25A MODEL OPTIONAL)		2. 
3	Frequency :	50/60 Hz, <u>+</u> 3%	50 / 60 Hz.		
4	Power Consumption :	30VA.	26VA.		
5	Output Relay Contacts :	1 CO	2CO		
6	Output Contact Rating :	5 A, 240 VAC (Resistive)	5 Amp, 240VAC [resistive]	ot	92
7	Life Expectancy :	0.5 x 10 <sup>6</sup> operations at 100% rating	0.5 x 10 operations at 100% rating	× 9 sl	- 38 -
8	OC Trip Setting :	$50\ \%$ to $140\%$ of rated Current Input $\ (variable)$	50 % TO 140% of rated current input variable ± 5 % w.r.t full scale	- <b>1</b> 5.2	
9	Under current trip setting	N.A	* 10 % to 100% of rated current input		
10	Set Accuracy :	<u>+</u> 5% w. r. t. Current Input of 100%	(variable) ± 5 % w.r.t full scale.		2.5
11	Trip Time Delay :	1 Sec. To 10 Sec. (Adjustable)	1 -10 sec ± 1 sec (Adj)		
12	Power on Delay:	3.5 Sec. <u>+</u> 1.5 Sec. (Fixed) REF. NOTE 01	1 -10 sec ± 1 sec (Adj).		
13	Reset :	Auto	Auto / Manual		
14	Reset Gap :	5% <u>+</u> 1% w.r.t. set current (Fixed)	10% ± 1% w.r.t. Set current (Fixed)		
15	Indications :	ON (Green) - Relay ON OC (Red) - Over Current TRIP	Power on (Green) - ON [For UC & OC Under current (Red) - UC fault respective Red Over current (Red) - OC LED Steady ON		
16	Current Sensor :	Inbuit 1 Amp & 5 Amp / (500 mA & 250 mA). Use external C.T. For more than rated current.	External CT having 5Amp or 1Amp secondary.		
17	Operating Conditions :	Temperature :5° C to 60°C	Temperature = - 5° c to + 60° c		
		Humidity :- Upto 95 % R. H.	Humidity = upto 95 % rh.		NOTE : • RELAY CONTACTS SHOWN FOR UNIT
18	Dimensions (mm) :	Overall : 76 x 30.5 x 117.5	Overall ( L X W X D) = 90 x 35 x 60	MONTORING OF 5 A / (500 mA) CURRENT INPUT IS SHOWN ABOVE. FOR MONITORIN	IG 1 A / (250 mA) OF CURRENT INPUT, TERMINALS 1 & 3 TO BE USED.
19	Weight (Approx.) :	350 gms.		R \$	L I
20	System supply voltage	110 / 220 / 230 / 240 VAC± 20 %	100 / 110 / 120 VAC± 20 % 220 / 230 / 240 VAC± 20 % 380 / 415 / 440 VAC± 20 %	B EXT. CT.(SA.(SOMA) SEC. RATINO)	
21	Enclosure :	ABS	S2 series - ABS / PC ABS		
22	Programming mode for [BY FRONT PUSH BUTTON]	NA	Test facility, Auto / manual Reset, NFS / FS facility, common or separate relay selection, ZCT or ZCH facility		NOTE : RELAY CONTACTS SHOWN FOR UNIT IN HEALTHY CONDITION. HOWN ABOVE BY USING EXT. CT. OF 5A (500 mA)

#### CONNECTION DIAGRAM OCS D1



WARRANTY - AGAINST ALL MANUFACTURING DEFECTS FOR 18 MONTHS FROM DATE OF SUPPLY OR 12 MONTHS FROM INSTALLATION WHICHEVER IS EARLIER

### www.minilecgroup.com

# minilec®

processing authorized

agencies. For more details contact us.

# INSTALLATION INSTRUCTION **CURRENT MONITORING RELAY**

#### **COMPLIANCE TO STANDARDS** OCS D1 S2 CMR5

	TEST	IEC STD.
1.	EFT Test of Auxiliary Supply	61000-4-4
2.	Surge Test of Auxiliary Supply	61000-4-5
3.	Voltage Interruption, Variation & Dip Test	61000-4-11
4.	ESD Test (Contact Discharge)	61000-4-2
5.	ESD Teast (Air Discharge)	61000-4-2
6.	H.V. Test (Dielectric Test)	60255-5
7.	Insulation Resistance Test	60255-5
8.	Dry Heat Test	60068-2-2
9.	Damp Heat test (Steady State)	60068-2-30
10.	Damp Heat test (cyclic test)	60068-2-78



Instructions for Screw Gun torque adjustment – • Torque should be 1 Nm max Max 2.5 sq. mm size wire car be used.

WARRANTY - AGAINST ALL MANUFACTURING DEFECTS FOR 18 MONTHS FROM DATE OF SUPPLY OR 12 MONTHS FROM INSTALLATION WHICHEVER IS EARLIER

# www.minilecgroup.com

Minilec (India) Pvt. Ltd.

Factory & Head Office: S. No. 1073/1-2-3, At Post: Pirangoot, Pune 412 111, India